

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33608
Name: W.D. Short Oil Co., LLC
Address 1: 102 S. River Rd.
Address 2: P.O. Box 729
City: Oxford State: KS Zip: 67119 + 8801
Contact Person: Don Short
Phone: (620) 455-3576
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E03386.1 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-02078-00-01
Spot Description: NW NW SE NW
~~S2 SW NE NW~~ Sec. 5 Twp. 34 S. R. 6 East West
4100 3903 Feet from North South Line of Section
1650 3660 Feet from East West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: Rahn Unit 1 Well #: 6
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 10-21-2011
Plugging Completed: 10-25-2011

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | SURF | 10 3/4 | 160 | -0- |
| | | P C | 6" | 2877 | -0- |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10-21-11: Open hole completion. Plugged back to 2300. Perf 2126 - 28, 2138 - 43. Run tubing to 2200. Spot 40 sk plug 2200 - 1920. Shot hole in 6" 40 sk cmt. Cmt fell--no circulation.
10-25-11: Run 1". Pumped 140 sk cmt 6" and 10 3/4. Circulate cmt to surface. Cmt ticket 33324, 33325

Plugging Contractor License #: 34271 Name: Kivett Plugging & Pipe Pulling, Inc.
Address 1: P O Box 577 Address 2: 402 N. 13th St.
City: Blackwell State: OK Zip: 74631 + 0577
Phone: (580) 763-7748
Name of Party Responsible for Plugging Fees: W.D. Short Oil Co., LLC
State of KANSAS County: Sumner, ss.
William D. Short, Jr. Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct to the best of my knowledge.

Signature: William D. Short, Jr.

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

NOV 21 2011

KCC WICHITA
AR