

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-20201-00-00
Spot: SENESE Sec/Twnshp/Rge: 2-32S-10E
2223 feet from S Section Line, 248 feet from E Section Line
Lease Name: ROGERS Well #: 2
County: CHAUTAUQUA Total Vertical Depth: 2369 feet

Operator License No.: 3591
Op Name: C & E OIL, LLC
Address: RR1 BOX 1B2
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	40		
PROD	7	2344		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2011 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ED TRIBOULET Company: _____ Phone: (620) 647-3601

Proposed Plugging Method: SURFACE CEMENT AND PRODUCTION CEMENT UNKNOWN. RUN 1" TO TD. GEL HOLE. SPOT 20 SX OF CEMENT ON BOTTOM. PULL OUT AND PERFORATE @ 1200' AND 550'. RUN BACK IN AND PLUG W/ 20 SX @ 1200'. PULL UP TO 550' AND CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed 09/22/2011 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 2150' gelled hole and spotted 20 sack plug. Pulled 1" and perforated at 1200' and 550'. Ran 1" back into 1200' and spotted 20 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 170 sacks of cement were used to plug this well.

RECEIVED
NOV 22 2011 DAS
KCC Chanute Dist #3

Perfs:

Remarks:

Plugged through: TBG

District: 03

Signed *Duane Sims*
(TECHNICIAN)

RECEIVED
NOV 28 2011
KCC WICHITA

11/30/11