

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20590-00-00
Spot: SENENWSW Sec/Twnshp/Rge: 35-3S-22W
2083 feet from S Section Line, 992 feet from W Section Line
Lease Name: TOWNSEND Well #: 1-35
County: NORTON Total Vertical Depth: 3885 feet

Operator License No.: 5455
Op Name: CRAWFORD OIL & GAS CO LLC
Address: PO BOX 1366 1780 JASON DR
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/15/2011 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Revd. from: JAY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE Witness Type: NONE
Date/Time Plugging Completed: 11/15/2011 3:30 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 2050' w/25 sxs.
2nd. Plug at 1220' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

Remarks: S.O.S. CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

CM

RECEIVED
NOV 28 2011
KCC WICHITA

Form CP-2/3

✓ 11/30/11

NOV 21 2011