

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23731-00-00
Spot: NESWNE Sec/Twnshp/Rge: 21-11S-15W
1767 feet from N Section Line, 1683 feet from E Section Line
Lease Name: EULERT RANCH "J" Well #: 3
County: RUSSELL Total Vertical Depth: 3426 feet

Operator License No.: 6194
Op Name: ESP DEVELOPMENT, INC.
Address: 1749 250TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	558	0	w/225 sxs cmt
PROD	5.5	3423	1739	w/130 sxs cmt

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/15/2011 11:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GLEN DINKEL Company: ESP DEVELOPMENT, INC. Phone: (785) 625-6394

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
Cut casing off at 1739' - leaving 1684' of 5 1/2" casing in the well.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2011 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing at 1739'.
Pulled casing to 1620' - pumped 160 sxs cement with 300# hulls.
Pulled casing to 990' - pumped 25 sxs cement.
Pulled casing to 600' - pumped 120 sxs cement - cement circulated.
POOH. Filled cellar and hole with 20 sxs cement.
Cellar and hole was full.
Visual check of well on 11/16/2011 - fluid down 90' to 100'.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #118.

Plugged through: CSG

RECEIVED
NOV 28 2011

KCC WICHITA

District: 04

Signed Ray Dinkel
(TECHNICIAN)

CM

Form CP-2/3

✓ 11/30/11

NOV 21 2011