

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21270-00-00
Spot: NESESENE Sec/Twnshp/Rge: 31-17S-10W
2000 feet from N Section Line, 150 feet from E Section Line
Lease Name: BOYS TOWN UNIT Well #: 1
County: ELLSWORTH Total Vertical Depth: 3256 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	321		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/23/2011 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: WES Company: SOUTHWIND DRILLING INC Phone: _____

Proposed Plugging Method: 35 SX ARB, 35 SX 1240', 35 SX 915', 35 SX 310', 25 SX 60'. 20 SX RH

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 11/23/2011 3:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

THE DRILL PIPE WAS RUN OPEN END TO TOP OF ARBUCKLE @ 3172' WHERE 35 SX OF CMT WAS SPOTTED. THE DRILL PIPE WAS PULLED TO 1240' WHERE 35 SX OF CMT WAS SPOTTED. PULLED DRILL PIPE TO 915', SPOTTED 35 SX CMT. PULLED DRILL PIPE TO 310', SPOTTED 35 SX CMT. PULLED DRILL PIPE TO 60' CIRCD 25 SX CMT. CIRCD 20 SX IN RAT HOLE.

Remarks: QUALITY WELL SERVICE #123, 60/40 4% GEL.

Plugged through: DP

District: 02

Signed _____

(TECHNICIAN)

RECEIVED CP-2/3
NOV 29 2011 4/30/11
KCC WICHITA