

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21351-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 34-30S-8W
1980 feet from N Section Line, 1040 feet from W Section Line
Lease Name: BOYLE K Well #: 4
County: KINGMAN Total Vertical Depth: 4545 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	253		225 SXS CMT
PROD	5.5	4543	1950	125 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: TOP PERFS 4344-4397, CIBP 4400. SAND TO 4290' & 5 SKS. REC PIPE, CIRC 300-0'. 35 SX 1200 35 SX 700

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/16/2011 9:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4290 & CAPPED WITH 5 SKS CMT. THE CASING WAS RECOVERED FROM 1950' & PULLED TO 1200', WHERE 35 SX CMT WAS SPOTTED. PULLED CASING TO 700', SPOTTED 35 SKS CMT. PULLED CASING TO 300' & CIRC CMT WITH 120 SKS CMT.

Perfs:

Top	Bot	Thru	Comments
4344	4397	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

11/30/11

1/2

RECEIVED
NOV 29 2011
KCC WICHITA