

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00622-00-00
Spot: NENESE Sec/Twnshp/Rge: 22-30S-8W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEST SPIVEY UNIT Well #: 38
County: KINGMAN Total Vertical Depth: 4378 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211		250 SX
PROD	5.5	4378	1875	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: SAND TO 4170' & 5 SKS. 35 SX 1200, 35 SX 700, CIRC 250-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/10/2011 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4172' & CAPPED WITH 5 SKS CMT. THE CASING WAS RECOVERED FROM 1875' & PULLED TO 1200', WHERE 35 SX CMT WAS SPOTTED. THE CASING WAS PULLED TO 700' WHERE 35 SX OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 250' WHERE CMT WAS CIRCUALTED TO SURFACE WITH 100 SX OF CMT.

Perfs:

Top	Bot	Thru	Comments
4230	4240	CSG	

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
NOV 29 2011
KCC WICHITA

JK