

To: 8 031263
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20, 890-00 01
JOka
SW SE SW, SEC. 15, T. 1 S, R. 27 W/E
330 feet from S section line
3630 feet from E section line

R

TECHNICIAN'S PLUGGING REPORT

Operator License 9860

Lease Name Huff Well # 1

Operator: Castle Resources
Name & Address Route 1 Box 90
Hays, Ks. 67601

County Decatur 107.84

Well Total Depth 3318 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated QWNO

Plugging Contractor Production Drilling License Number _____

Address Hays, Kansas

Company to plug at: Hour: PM Day: 2 Month: June Year: 19 - 89

Plugging proposal received from Jerry Green

(company name) Castle (phone) _____

were: 8 5/8" set at 212' w/150 sks cwc. 5 1/2" set at 3577' w/110 sks. PBSD 3318'.

~~Order sand and common cement. Pull pipe. Order 200 cks 65/35 poz 10% gel.~~
~~Halliburton Cement Co.~~

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 2 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Sand bottom back to 3208'. Spot 5 sks

common cement on sand w/bailer. 2 shots. at 1930' anhy. Shot off freepoint at 985'. Laid

down two joints of 5 1/2". Pumped down 5 1/2" w/100 sks cement blend w/400# hulls. Pulled rest of
casing. Squeezed 8 5/8" casing w/total of 200sks cement blend to max psi 200#. Close in 150#.

Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1989

Remarks: Con Butcher and ~~_____~~ gave orders.
(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I hereby advise you to observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

ES

DATE 6-23-89
INV. NO. 25106