

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20615-00-00  
Spot: SESEWNWE Sec/Twnshp/Rge: 5-33S-16W  
1281 feet from N Section Line, 1563 feet from E Section Line  
Lease Name: EDEN A Well #: 2-5  
County: COMANCHE Total Vertical Depth: 5066 feet

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 W 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	419		WITH 300 SX CMT
PROD	4.5	5063	3046	WITH 200 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2011 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: PUMP 50 SX CMT INTO PERFS THRU TBG. BACK OFF/SHOOT OFF TBG. SHOOT OFF CSG/RIP. PLUG AT 900' WITH 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 11/16/2011 12:45 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 75 SX CMT INTO PERFS THROUGH TBG. SHOT OFF TBG AT 3500'. RIPPED CASING AT 3046'. 1ST PLUG AT 900' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5005	5010		MISSISSIPPI
4992	4997		MISSISSIPPI

RECEIVED  
DEC 01 2011  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Ken Jehlik  
(TECHNICIAN)

RECEIVED  
NOV 18 2011  
KCC DODGE CITY

Form 512-3

12/02/11