

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22593-00-00
Spot: N2NENW Sec/Twnshp/Rge: 2-35S-14W
490 feet from N Section Line, 1980 feet from W Section Line
Lease Name: LUKENS Well #: 1-2
County: BARBER Total Vertical Depth: 4973 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3950		WITH 2 SX CMT
CIBP		4750		WITH 2 SX CMT
SURF	8.625	425		WITH 300 SX CMT
PROD	4.5	4970	2500	WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/16/2011 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP'S @ 4750' & 3950' WITH 2 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 11/16/2011 12:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SET CIBP @ 4750' WITH 2 SX CMT. SET CIBP @ 3950' WITH 2 SX CMT. 1ST PLUG AT 1008' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 441' WITH 50 SX CMT. 3RD PLUG AT 55' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4840	4854		MISSISSIPPI
4820	4824		CHEROKEE
4662	4666		KANSAS CITY L
4175	4180		KANSAS CITY A
4003	4008		O'READ

RECEIVED
DEC 01 2011
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

RECEIVED
NOV 22 2011
KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

Form CP-2/3

12/02/11