

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20462-00-00  
Spot: SENW Sec/Twnshp/Rge: 20-23S-19W  
3305 feet from S Section Line, 3287 feet from E Section Line  
Lease Name: LIPPOLDT A Well #: 1-20  
County: EDWARDS Total Vertical Depth: 2620 feet

Operator License No.: 34255  
Op Name: JRC PRODUCTION, LLC  
Address: 746 E 520TH AVE  
PITTSBURG, KS 66762

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	250		WITH 225 SX CMT
PROD	4.5	2612	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2011 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JIM EWERS Company: JRC PRODUCTION Phone: (918) 945-4463

Proposed Plugging Method: PUMP 40SX CMT @ 2500' THROUGH TBG. PERFORATE 4 1/2" @ 1250'. RUN TBG TO 1250'. CIRCULATE CMT TO SURFACE UP 4 1/2" AND 7" X 4 1/2" ANNULUS. TRIP OUT PIPE & TOP OFF HOLE WITH CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/04/2011 1:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 8 SX GEL - 40 SX CMT AT 2573'. PULLED TBG TO 1984' & COMPANY SHUT DOWN DUE TO SNOW STORM. 11/3/11: COMPANY SHOWED UP AT 10:00 AM. TBG STUCK IN HOLE DUE TO NOT BEING PULLED OUT OF CMT THE NIGHT BEFORE. SHOT OFF 2 3/8" TBG AT 1297'. PULLED TBG TO 1235'. PERFORATED 2 3/8" & 4 1/2" @ 1234.5'. 11/4/11: CMT SHOWED UP AT 12:15 PM. PUMPED 105 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 4 1/2". COMPANY TOPPED OFF 4 1/2" WITH 10 SX CMT. COMPANY REFUSED TO PULL TBG OUT OF HOLE. PRESSURED 7" X 4 1/2" ANNULUS TO 600 PSIG WITH 50 SX CMT. SHUT IN PRESSURE 350 PSIG.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
NOV 22 2011  
KCC DODGE CITY

Form CP-2/3

12/02/11

Rec'd  
12-1-11  
KCC Wichita