

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

K.A.R.-62-3-117

API NUMBER 15-071-20,074-00-00

LEASE NAME Toadvine

WELL NUMBER 1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 36 TWP. 19 RGE. 40 CORNER (X)

COUNTY Greeley

Date Well Completed 11-22-74

Plugging Commenced 7-25-97

Plugging Completed 7-25-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR W.R. Williams

ADDRESS P.O. Box 15163, Amarillo, TX 79105

PHONE# (806) 374-4555 OPERATORS LICENSE NO. 31709

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 18, 1997 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation Upper Winfield Depth to ^(Perf) Top 2846 Bottom 2854 T.O. 2980

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Upper Winfield	Gas	0	229	8-5/8	229	0
2832-2854		0	2980	4-1/2	2980	1000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set:

- Plug #1 25 sx 2825'-2496'
- Plug #2 80 sx 2300'-1400' Perf'd casing @ 1400'
- Plug #3 50 sx 600'-426'
- Plug #4 50 sx 260'-90'
- Plug #5 10 sx 40'-0'

Name of Plugging Contractor Allied Cementing License No. 08-01-97

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W.R. Williams

STATE OF Texas COUNTY OF Potter, ss.


W.R. Williams, Operator (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) W.R. Williams

(Address) P.O. Box 15163, Amarillo, TX 79105

Subscribed and sworn to before me this 30 day of July, 19 97

Linda K. McKean
Notary Public



My Commission Expires: 10-30-99

USE ONLY ONE SIDE OF EACH FORM