


15-071-20053-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plot

Greeley County. Sec 34 Twp 19S Rge. 40W (By W)
Location as "NE/CNW/SW" or footage from lines C NE/4
Lease Owner Dorchester Exploration, Inc.
Lease Name Wineinger "A" #1 Well No. 1
Office Address 1204 Vaughn Building, Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 13, 1974 19
Application for plugging filed March 12, 1974 19
Application for plugging approved March 12, 1974 19
Plugging commenced 4:00 AM, March 13, 1974 19
Plugging completed 5:00 AM, March 13, 1974 19
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2950' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
150 sacks cement at 1100' through open end
of drill pipe; 50 sacks at 250' through open
end of drill pipe; 12 sacks at 40' to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1974

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579


STATE OF KANSAS COUNTY OF RICE ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and Sworn to before me this 16th day of March, 19 74.



CHARLES HALL—NOTARY PUBLIC
My Commission Expires Jan. 8, 1978

Charles M. Hall
Charles M. Hall, Notary Public.

15-071-20053-00-00

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- WINEINGER "A" #1
Located: C NE/4, Section 34-19S-40W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 8, 1974
COMPLETED: March 13, 1974

TOTAL DEPTH: 2950'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 950	Sand and Shale	Ran 5 joints new 8rd, 8 5/8", 20#, Range 3 casing, 232.29' set at 243' K.B. with 160 sacks Common, 3% cc. Plug down at 9:55 PM, 3-8-74.
950 - 1475	Shale and Shells	
1475 - 1918	Shale and Sand	
1915 - 2295	Shale and Lime	
2295 - 2486	Shale and Sand	
2486 - 2506	Anhy.	
2506 - 2516	Shale	
2516 - 2685	Shale and Shells	
2685 - 2950	Lime and Shale	Plugged.

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1974
CONSERVATION DIVISION
Wichita, Kansas