

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-071-20285 - 00-00
LEASE NAME KS. AGRICULTURAL UNIT
WELL NUMBER 1

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

3960 Ft. from S Section Line
3960 from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc.
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202
PHONE # () 267-3241 OPERATORS LICENSE NO. 30606
Character of Well Gas (Oil, Gas, D&A, SWD, Input, Water Supply Well)
Plugging Completed 4/2/99

SEC. 29 TWP. 19S RGE. 40W(E) or (W)
COUNTY Greeley
Date Well Completed 6/14/83

Plugging commenced 4/2/99

The plugging proposal was approved on _____ (date)
by _____ (KCC District Agent's Name).

Is ACO-i filed? Yes If not, is well log attached? No

Producing Formation Chase Depth to Top 2892 Bottom 2971 TD _____

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1285	
				5 1/2	4771	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Put led bottom of tub to 2822'. Perfs 2892-2972. Placed 25sx 60/40 Poz 6% gel w/100# hulls @ 2822'. Pulled tbg to 1437'. Loaded hole w/24BFW. Pumped 175 sxs. 60/40 Poz. 6%gel @1437'. TOH w/ remaining 46jts.tbg. Tied onto 5 1/2 /8 5/8" annulus and pumped 110 sxs. 60/40 Poz. 6%gel. Topped off 5 1/2" csg. w/25 sxs 60/40 Poz. 6%gel.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK ,ss.

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M. Jack
(Address) Wichita, KS

RECEIVED
STATE CORPORATION COMMISSION

05-06-99
MAY 06 1999



CONSERVATION DIVISION
Public - Wichita, Kansas

My Commission Expires: 2/6/02

Kerran Redington Notary