

15-071-20027-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Greeley County. Sec. 8 Twp. 19S Rge. 40 (E) X (W)
Location as "NE/CNWSW" or footage from lines C SE/4
Lease Owner Dorchester Exploration Incorporated
Lease Name Vogleman Well No. 1
Office Address 1204 Vaughn Building; Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Gas- dry hole
Date well completed August 23, 1973 19 73
Application for plugging filed October 18 19 73
Application for plugging approved October 19 19 73
Plugging commenced October 24 19 73
Plugging completed October 24 19 73
Reason for abandonment of well or producing formation non- commercial



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production X 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Chase Depth to top 2893 Bottom 2953 Total Depth of Well 2953 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Chase	Gas and water	2893	2953	4 1/2"	2938	940

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

25 sacks cement- pumped 2060 to 2360
mud 2060 to 940
cement- 140 cubic feet from 940 to 675
mud from 675 to 370
cement- 45 cubic feet from 370 to 295
mud from 295 to 25 feet
cement from 25 feet to 4 feet
10 3/4" casing cut off at 4'- weld plate on top

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton
Address Liberal, Kansas


STATE OF Kansas COUNTY OF Seward ss.
R. L. Higginbottom (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Higginbottom
Box 6; Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of November, 19 73

A. J. Parnell
Notary Public.

My commission expires AUGUST 1977

 STATE NOTARY PUBLIC
 Seward County, Kansas
 My Commission Expires
 June 6, 1977

15-071-20027-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1973
CONSERVATION DIVISION
Wichita, Kansas

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- VOGELMAN #1
Located: SE/4, Section 8-19S-40W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 27, 1973
COMPLETED: March 5, 1973

TOTAL DEPTH: 2938'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 2514	Sand and Shale	Ran 11 joints 10 3/4" casing, 343.19' set at 351.19' K.B., one centralizer, cemented with 150 sacks Howco Light, 1/4 sack floreal per sack, 3% cc, followed with 150 sacks Pozmix with 3% cc. Plug down at 3:50 AM, 2-28-73.
2514 - 2534	Anhy.	
2534 - 2893	Shale and Sand	
2893 - 2938	Lime and Shale	Ran 95 joints 4 1/2" Pipe, 2947' set at 2938' K.B. with 150 sacks Common with 2% gel. Plug down at 3:30 PM, 3-5-73.