

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 207B
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20637-01-00

LEASE NAME Koch

WELL NUMBER 2H

4290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 7 TWP. 19S RGE. 40 W

COUNTY Greeley

Date Well Completed 3-3-95

Plugging Commenced 9-18-01

Plugging Completed 9-19-01

RECEIVED
OCT 15 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR W.R. Williams, Inc.

ADDRESS P.O. Box 15163 Amarillo, TX 79105

PHONE# (806) 374-4555 OPERATORS LICENSE NO. 32920

Character of Well D&A Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on +/- Sep. 5, 2001 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? unknown If not, is well log attached? Log Attached to CP-1

Producing Formation None Depth to Top _____ Bottom T.O. 2911

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13-3/8	242	0
				9-5/8	2520	0
				5-1/2	2955	2016

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 2900' with 2 sacks cement on top, shot off 5-1/2" @ 2016', spotted plugs as follows: 50 sx @ 1500', 50 sx @ 750', 50 sx @ 400', 15 sx @ 40'.

Name of Plugging Contractor Allied Cementing License No. N/R

Address Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: W.R. Williams, Inc.

STATE OF Texas COUNTY OF Potter, ss.

W. Rob Williams, President of W.R. Williams, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) W. Rob Williams

(Address) PO Box 15163, Amarillo, TX 79105

SUBSCRIBED AND SWORN TO before me this 11 day of October, 2001

Linda K McKean
Notary Public

My Commission Expires: 10-30-2003



OR