

LEASE NAME Floyd

WELL NUMBER #1

SPOT LOCATION C SW

SEC. 24 TWP. 19 RGE. 40 (X) or (W)

COUNTY Greeley

Date Well Completed 3-74

Plugging Commenced 8-22-1988

Plugging Completed 8-24-1988

TYPE OR PRINT  
NOTICE: Fill out complotoly  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hughes Seewald

ADDRESS Box 2587, Liberal, Ks: 67905

PHONE (316) 624 3767 OPERATORS LICENSE NO. 9922

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes if not, is well log attached? \_\_\_\_\_

Producing formation Winfield Depth to top 2815 bottom 2840 T.D. 2895

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled
Surface				8 5/8"	242'	0'
Production				4 1/2"		1046'

RECEIVED

JUL 17 1989

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 20 sks. cement to 2600' pressured to 500 lbs.

Pump 40 sks. cement 1046' to 946' - Mud 946' to 270'

Pump 40 sks. cement 270' to 170'

Put bridge and 10 sks. cement 40' to 3'

Cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (~~XXXXXXXXXXXXXXXXXXXX~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves  
(Address) Box F, Sublette, Ks. 67877

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1988

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-88

