


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-071-00021-00-00

NORTH



Locate well correctly on above  
Section Plat

Greeley County, Sec. 18 Twp. 19-S Rge. 40-W (25) (W)

Location as "NE/CNW/SW" or footage from lines C SW SW

Lease Owner General Crude Oil Co. & Van-Grisso Oil Co.

Lease Name W. Edman Well No. 1

Office Address 314 Commerce Bldg., Abilene, Texas & 1012 City Nat'l Bldg., Okla. City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Gas w/too much water.

Date well completed August 23, 19 57

Application for plugging filed November 27, 19 57

Application for plugging approved November 29, 19 57

Plugging commenced December 10, 19 57

Plugging completed December 11, 19 57

Reason for abandonment of well or producing formation Well was not a commercial producer of gas and also produced excessive water.

If a producing well is abandoned, date of last production Never produced 19     

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Don Truan, Rt. 1, Russell, Kansas

Producing formation Winfield Depth to top 2877 Bottom 2920 Total Depth of Well 4042 Feet

Show depth and thickness of all water, oil and gas formations. PBTB 3010

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dakota	Water	944	1018	10-3/4"	411	None
Cheyenne	Water	1120	1164	5", 15"	3010	None
Winfield	Salt Water & Gas	2877	2920			
Ft. Riley	Salt Water	2936	2980			
Admire	Salt Water	3560	3570			
Waubaussee	Sulfur Water	3750	3790			
Shawnee	Salt Water	3904	3916			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Cement plugs from 3977' to 4042'; 3740 to 3820'; 3115 to 3180' w/heavy mud between plugs. These cement plugs were pumped through the drill pipe by Halliburton. 5-1/2", 15.5# casing was set at 3010' w/float collar at 2979' & the joint of casing between the guide shoe and float collar is full of cement. Set sand plug from 2979' to 2900' by dumping through casing & measuring fillup w/wire line & odometer. Set cement plug from 2815' to 2900' by dumping & measuring w/wire line & odometer. Filled w/mud to 1000' and pushed a wood plug down & dumped rock on the wood plug. Set cement plug from 898' to 1000' w/dump bailer. Filled w/mud to 300' and set wood plug by pushing to 300' w/bailer. Set cement plug from 300' to 3'. Cut off pipe & welded steel plate over casing below plow depth of 3'.

All work of plugging the well through the casing was performed by West Supply Company, Inc. (Plugging License No. 14) Chase, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 16 1957

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company, Inc. (Plugging License No. 14) Wichita, Kansas  
Address Chase, Kansas

STATE OF Texas COUNTY OF Taylor, ss.  
Charles E. Jones (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles E. Jones Charles E. Jones  
314 Commerce Bldg., Abilene, Texas  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 57

Martha Wishert Martha Wishert  
Notary Public.

My commission expires 6-1-59

PLUGGING  
TR. NO. 18 T. 19 R. 40W  
BOOK PAGE 64 LINE 16

15-071-00021-00 00

CERTIFIED DRILLER'S LOG  
GENERAL CRUDE OIL COMPANY & VAN-GRISSE OIL COMPANY  
NO. 1 W. EDMAN WELL, GREELEY COUNTY, KANSAS

Location: The subject well is located in C SW SW Section 18, T19S, R40W, Greeley County, Kansas.

<u>Depth</u>	<u>Description</u>
0- 200	Surface sands and clays.
200- 595	Shale.
595- 944	Shale and sand.
944-1010	Sand (Dakota).
1010-1120	Shale and lime.
1120-1164	Sand (Cheyenne).
1164-1685	Shale and lime.
1685-2724	Redbed and shale.
2724-2896	Redbed, shale and lime streaks.
2896-2979	Lime and redbed.
2979-3264	Sandy shale and redbed
3264-4042	Lime and shale (Total Depth).

AFFIDAVIT

STATE OF TEXAS, COUNTY OF TAYLOR, SS,

I, Charles E. Jones of the General Crude Oil Company, being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Charles E. Jones  
Charles E. Jones

Subscribed and sworn to before me this 14th day of October, 1957.

Martha Wiskent  
Notary Public in and for Taylor County, Texas.

PLUG 18  
SEC 18 19 40W  
T19S R40W 64 16