

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-071-20,049-00-00

LEASE NAME Simpson

WELL NUMBER 1

SPOT LOCATION C NE/4

SEC. 23 TWP. 19S RGE 41 (X) or ()

COUNTY Greeley

Date Well Completed 11-29-73

Plugging Commenced 4-2-86

Plugging Completed 4-3-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Damson Oil Corporation

ADDRESS P. O. Box 750, Amarillo, Texas 79105

PHONE # (806) 353-2161 OPERATORS LICENSE NO. 08098

Character of Well Gas
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? No (Attached to CP-1)

Producing formation Lower Winfield Depth to top 2873 bottom 2888 T.O. 2950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	241'	8 5/8	233'	None
		Surface	2949	5 1/2	2941'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. The pump & plug method was used to plug the 5 1/2" casing as follows: (1) Pump 5 bbl 9# mud (2) Pump 5 bbl 9# mud w/50# cotton seed hulls (3) Pump 3 bbl class H cmt (4) Pump 60 bbl mud (5) Pump 5 bbl class H cmt. 3 bbl class H cmt was pumped down the 8 5/8"-5 1/2" annulus until full. 8 5/8" & 5 1/2" were cut off 4' below gr level & capped. The pump & plug method placed cement plugs from: surface to 205' and from 2664' to 2787' w/9# mud in between.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. NA
Address Lamar, Colorado

STATE OF _____ COUNTY OF _____, ss.

_____, (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Bill Mallan

(Address) _____

SUBSCRIBED AND SWORN TO before me this 28 day of April 1986.

Commission expires: 8-28-88

STATE CORPORATION COMMISSION
MAY 01 1986
CONSERVATION DIVISION
Wichita, Kansas

Ida Smith

NOV 5 1984

GEOLOGY

DAMSON OIL CORPORATION
SOLD PROPERTY 15-071-20049-00-00

ENGINEERING WELL FILE

PERMANENT



KS-38

Well File



COMPANY DORCHESTER EXPLORATION, INC.
WELL SIMPSON # 1
FIELD BRADSHAW
County GREELEY State KANSAS

DORCHESTER EXPLORATION, I

WELL SIMPSON # 1
FIELD BRADSHAW
COUNTY GREELEY STATE KANSAS

Location C NE/4 Other

Sec. 23 Twp 19S Rge 41W

Permanent Datum GROUND LEVEL Elev. 3651'
Log Measured From KELLY BUSHING, 10 Ft. Above Perm. Datum
Drilling Measured From KELLY BUSHING

Date	11-28-73			
Run No.	ONE			
Depth-Driller	2950'			
Depth-Welex	2950'			
Btm. Log Inter.	2943'			
Top Log Inter.	250'			
Casing-Driller	8 5/8" @ 242'	@	@	
Casing-Welex	250'			
Bit Size	7-7/8"			
Type Fluid in Hole	W. B. MUD SALT GEL			
Dens. Visc.	10.4 34			
pH Fluid Loss	6.4 6.0ml	ml	ml	
Source of Sample	CIRCULATED			
R ₁₀₀ @ Meas. Temp.	0.10 @ 60°F	@ °F	@ °F	
R ₅₀₀ @ Meas. Temp.	0.08 @ 60°F	@ °F	@ °F	
R ₁₀₀₀ @ Meas. Temp.	0.12 @ 60°F	@ °F	@ °F	
Source R ₁₀₀ R ₅₀₀ R ₁₀₀₀	MEAS. MEAS.			
R ₁₀₀ @ BHT	0.05 @ 96°F	@ °F	@ °F	
Time Since Circ.	---			
Max. Rec. Temp.	96°F @ 2940'	HEAVY LEVEL		
Equip Location	7579 IPARPA	STATE CORPORATION COMMISSION		
Recorded By	WHITE-REEVES	FEB 26 1985		
Witnessed By	MR. HIGGINS			

CONSERVATION DIVISION
Wichita, Kansas