


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-071-00020-00-00

NORTH



Locate well correctly on above  
Section Plat

Greeley County, Sec. 17 Twp. 19 Rge. 41 (E) W (W)

Location as "NE/CNW/SE/SW" or footage from lines C NE SW  
Lease Owner Honaker-Davis Drlg. Co.  
Lease Name Pearson #1 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed 10-12-57 19\_\_\_\_  
Application for plugging filed 10-21-57 19\_\_\_\_  
Application for plugging approved 10-23-57 (letter) 19\_\_\_\_  
Plugging commenced 12-4-57 19\_\_\_\_  
Plugging completed 12-7-57 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well D. Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5412 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	2988'	1393'
				12-3/4"	256'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole and found it open. Filled w/sand to 2860' and ran 10 sacks of cement. Pulled 8" casing. Mudded the hole to 266', set a rock bridge and ran 35 sacks of cement. Mudded the hole to 35', set a rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1957

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

\_\_\_\_\_(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 57

[Signature]  
Notary Public.

My commission expires 9-27-58

PLUGGING  
DEC 17 1957  
56124

DRILLERS' LOG

Pearson No. 1  
Loc: Ctr. NE SW  
Sec: 17-19S-41W  
Greeley County, Kansas  
Company: Menaker-Davis Drig. Co., et al  
Contractor: Menaker-Davis Drig. Co.

Comm: 7-29-57  
Comp: 8-20-57  
Rotary Total Depth: 5412'  
Casing: 12-3/4" at 256'  
8-5/8" at 2988'

0	60	Clay
60	160	Sand
160	317	Black Shale
317	1340	Blue Shale
1340	1395	Shale & Shells
1395	1450	Lime
1450	1545	Shale & Lime
1545	1850	Red Bed & Shale
1850	1900	Shale & Red Bed
1900	1930	Lime & Shale
1930	2095	Shale & Red Bed
2095	2265	Shale & Lime
2265	2850	Lime & Shale
2850	2875	Sand & Shale
2875	2916	Shale & Sand
2916	2970	Sand & Shale
2970	2990	Shale & Lime
2990	4595	Lime & Shale
4595	4667	Lime & Chert
4667	4745	Lime & Shale
4745	4780	Lime
4780	4933	Lime & Shale
4933	4985	Lime, Shale & Chert
4985	5030	Lime & Shale
5030	5135	Shale & Lime
5135	5253	Lime & Shale
5253	5312	Lime & Chert
5312	5343	Lime
5343	5412	Lime & Chert
5412		Total Rotary Depth

12-3/4" casing cemented at 256' with 250 sacks common cement and 2% calcium chloride.

8-5/8" casing cemented at 2988' with 400 sacks common cement and 2% calcium chloride.

No casing was run at total depth.

RECORDED  
INDEXED  
DIVISION  
1957

I certify that this is the true and correct copy of the above log to the best of my knowledge.

*H. S. Forbes*  
H. S. Forbes

Subscribed and sworn to before me this 26th day of August, 1957.

*Kenneth G. Fischer*  
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING  
FILE SEC 17 T 19 R 41W  
BOOK PAGE 56 LINE 4