


15-671-20020-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Greeley County, Sec 31 Twp 19S Rge. 40W (E)X (W)
Location as "NE/CNW/SW" or footage from lines C SE
Lease Owner Dorchester Exploration, Inc.
Lease Name Campbell #1 Well No. 1
Office Address 1204 Vaughn Building, Midland, Texas 79701
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 29, 1973 19
Application for plugging filed January 29, 1973 19
Application for plugging approved January 29, 1973 19
Plugging commenced 9:00 PM, January 29, 1973 19
Plugging completed 11:00 PM, January 29, 1973 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2930' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	365'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud.
Plug at 1225' through open end of drill pipe,
140 cu. ft. of 50/50 Pozmix, 6% gel. #2 plug
through open end of drill pipe at 400', with
140 cu. ft. of 50/50 Pozmix, 6% gel. Howco plug
and 1/2 sack hulls at 40' with 20 cu. ft. of 50/50
Pozmix, 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Mellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Mellner
F. A. Mellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of February, 19 73

NOTARY PUBLIC
My Commission Expires 12, 1974
My commission expires _____

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

15-071-20020-00-00

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- CAMPBELL #1
Located: C SE, Section 13-19S-40W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: January 23, 1973
COMPLETED: January 29, 1973

TOTAL DEPTH: 2930'

<u>LOG</u>	
0 - 366	Shale and Sand
366 - 615	Shale
615 - 1106	Shale and Lime
1106 - 1585	Shale and Sand
1585 - 1940	Lime and Shale
1940 - 2200	Shale and Sand
2200 - 2553	Shale and Anhy.
2553 - 2580	Shale
2580 - 2900	Shale and Anhy.
2900 - 2930	Lime and Shale

CASING RECORD

Ran 8 joints 10 3/4", 8rd, 32#, Rgc #3,
new casing, 356.60' set at 365' K.E.
with 150 sacks Howco Light with 2%
cc, followed with 150 sacks Common with
3% cc. Plug down at 2:15 AM, 1-24-73
by Howco.

Plugged.

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION
Wichita, Kansas