


15-871-20028-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Greeley County, Sec. 12 Twp. 19 Rge. 41 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
----- C SW 1/4
Lease Owner Dorchester Exploration Inc.
Lease Name Floyd Well No. 1
Office Address 1204 Vaughn Bldg., Midland Texas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above Section Plat

Gas
Date Well completed _____ 19
Application for plugging filed 7-27-1976 19
Application for plugging approved 8-3-1976 19
Plugging commenced 8-4-1976 19
Plugging completed 8-6-1976 19
Reason for abandonment of well or producing formation
Non Commercial
If a producing well is abandoned, date of last production
Never Produced 19
Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Balthazor
Producing formation Hugoton Depth to top 2912 Bottom 2922 Total Depth of Well 2950'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0'	225'	8 5/8"	225'	0'
Hugoton		0'	2949'	4 1/2"	2949'	590'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 1 sacks hulls & 10 sacks cement to 2760'
Mud 2760' to 590'
Pumped 20 sacks cement 590' to 530'
Mud 530' to 225'
Pumped 35 sacks cement 225' to 125'
Mud 125' to 40'
Bridge & 10 sacks cement 40' to 0',
Cut off 8 5/8" 42" below ground level.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling

STATE OF Kansas COUNTY OF Haskell ss.
Edgar J. Eves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Kansas 67877
(Address)

Subscribed and sworn to before me this 9 day of aug. 1976

My commission expires _____
David H. Ringhart Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1976

CONSERVATION DIVISION
Wichita, Kansas

15-071-20028-00-00

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- FLOYD #1
Located: SW/4, Section 12-19E-41W, Greeley County, Kansas

OWNER: Dorchester Exploration, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 10, 1973
COMPLETED: September 14, 1973

TOTAL DEPTH: 2950'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 130 Sand and Clay	Ran 7 joints 8 5/8" casing, 214' pipe set at 225' K.B. Cemented with 100 sacks Halliburton light with 3" cc, followed with 100 sacks Pozmix, 3 3/4 cc. Plug down at 6:15 PM, 9-10-73.
130 - 500 Shale	
500 - 1240 Lime and Shale	
1240 - 1800 Shale, Sand, Salt	
1800 - 1940 Shale and Sand	
1940 - 2360 Shale and Gyp.	
2360 - 2481 Shale	
2481 - 2502 Anhydrite	
2502 - 2950 Lime and Shale	Ran 75 joints 4 1/2" OD casing, 2964' pipe cemented at 2950' with 600 sacks Light weight, following with 150 sacks Pozmix. Plug down at 2:15 PM, 9-14-73.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1976

CONSERVATION DIVISION
Wichita, Kansas

Original +1
to Midland
9/27/73