

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-071-20567-00-00

LEASE NAME Matney

WELL NUMBER 1-32

350 Ft. from S Section Line

2278 Ft. from E Section Line

SEC. 32 TWP. 19S RGE. 42 (R) or (W)

COUNTY Greeley

Date Well Completed N/A

Plugging Commenced 8/11/92

Plugging Completed 8/12/92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Marathon Oil Company

ADDRESS P. O. Box 2690, Cody, WY 82414

PHONE# (307) 587-4961 OPERATORS LICENSE NO. 30689

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 11, 1992 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? With CP-4 If not, is well log attached? Logs Included

Producing Formation N/A Depth to Top -- Bottom -- T.D. 5350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surface	To	Size	Put In	Pulled out
Morrow Sand	Water		286'	8-5/8"	0'-286'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Filled hole with mud from 5350'-2486'. Set cement plug #1 from 2486'-2286' (60 sxs.). Set mud spacer from 2286'-1650'. Set cement plug #2 from 1650'-1350' (90 sxs.). Set mud spacer from 1350'-798'. Set cement plug #3 from 798'-598' (60 sxs.). Set mud spacer from 598'-332'. Set cement plug #4 from 332'-132' (60 sxs.). Set mud spacer from 132'-49'. Set cement plug #5 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Drilling License 7846

Address P. O. Box 916, 3490 West Jones Ave., Garden City, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Marathon Oil Company

STATE OF Wyoming COUNTY OF Park

Randal P. Meabon (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R P Meabon

(Address) P. O. Box 2690, Cody, WY 82414

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 92  
Connie A. Shanks  
Notary Public  
Expires: 9-6-1992



RECEIVED  
AUG 24 1992  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Report (Cont.)

from 49'-surface (15 sxs.). Filled rat hole with 15 sxs. of cement. Filled mouse hole with 10 sxs. of cement. All cement used for plugging operations was 60-40 Pozmix containing 6% gel and 1/4#/sx. Flo-Seal.

Dist: KCC- Orig. & 2cc, WRF, MEB, WTR, JRW, Lamar, Account., Draft., Land, Title & Cont. (Hou.)