


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Greeley County. Sec. 9 Twp. 19S Rge. 42W (E) (W)
Location as "NE/CNW&SW%" or footage from lines SW/4 NE/4
Lease Owner Mack Oil Company
Lease Name Gano Unit Well No. 1
Office Address 812 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 7 1961
Application for plugging filed November 13 1961
Application for plugging approved November 13 1961
Plugging commenced December 4 1961
Plugging completed December 5 1961
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.
Producing formation None Depth to top Bottom Total Depth of Well 3125 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface sand & gravel	water	0	151	8 5/8	151	None
Permian Sand	water	0	3093	4 1/2	3093	1738

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with sand from 2830' to 2775' and with 4 sacks cement on top of sand.
Plugged at 190' with 20 sacks cement.
Plugged at 30' with 10 sacks cement.

RECORDED
STATE CORPORATION COMMISSION

12-18-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Mack Oil Company
Address Box 471, Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert L. Harris (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Harris
812 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of December, 1961

Eudora Lee Buschman

My commission expires September 8, 1963

Notary Public.



15-071-00005-00-00

MACK OIL COMPANY
Duncan, Oklahoma

DRILLERS WELL LOG

Gano Unit #1 C SW NE Sec. 9-19-42W
Greeley County, Kansas
Commenced R.D.: 8-26-61 Elevation: 3826 K.B.
Completed R.D.: 8-30-61 Initial Production:
Total Depth: 3125 Contractor: Mack Oil Company

Casing Record: 151' 8 5/8" O.D. Surface Casing
3093' 4 1/2" Production Casing

<u>STRATA</u>	<u>DEPTH</u>
Clay	0 - 26
Shale	26 - 155
Clay and Shale	155 - 1100
Sand	1100 - 1150
Shale and Shells	1150 - 1602
Anhydrite and Shale	1602 - 1675
Shale and shells	1675 - 1962
Anhydrite and Shells	1962 - 1990
Shale and Shells	1990 - 2512
Anhydrite	2512 - 2538
Shale and Shells	2538 - 3050
Lime and Shale	3050 - 3125

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL COMPANY

By Robert L. Harris

Signed and sworn to in my presence this 13th day of November, 1961, by Robert L. Harris, representative of Mack Oil Company.

Eudora Rae Barackman
Eudora Rae Barackman
Notary Public

My commission expires September 8, 1963.