


15-171-00063-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Scott County, Sec. 35 Twp. 18S Rge. 34W (X) (W)

Location as "NE/CNW%SW%" or footage from lines C NE NW
Lease Owner D. G. Hamilton
Lease Name Latzke Well No. 1
Office Address 1001 Union Center
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed August 16 1962
Application for plugging filed August 16 1962
Application for plugging approved August 16 1962
Plugging commenced August 16 1962
Plugging completed August 16 1962
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5046 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	324'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud to 315'
Hulls, plug 20 sx thru DP
Mud to 35' Hulls, Plug 10 sx
25 sx in rathole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine Head (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine Head

580 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of August, 1962

Jean Kollar

Notary Public.



15-171-00063-00-00

DRILLERS LOG

Latzke No. 1

CASING RECORD: 8 5/8" @ 324' w/200 sx cement
 COMPANY: D. G. Hamilton
 CONTRACTOR: Red Tiger Drilling Co.
 COMMENCED: July 30, 1962
 COMPLETED: August 16, 1962
 DESCRIPTION: C NE NW 35-18S-34W Scott Co., Kansas
 ELEVATION:


TOTAL DEPTH: 5046'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Rock	0	120	
Sand & Gravel	120	135	
Shale	135	380	
Chalky Sand & Lime	380	450	
Shale	450	825	
Sand Shale & Shells	825	1275	
Red Bed & Shale	1275	1673	
Anhydrite	1673	1694	
Red Bed Shale & Salt	1694	1960	
Sand	1960	2040	
Shale	2040	2095	
Shale & Shells	2095	2580	
Shale & Salt	2580	2721	
Salt & Sandy Dol.	2721	2850	
Shale & Lime	2850	3280	
Slightly Sandy Lime & Shale	3280	3384	
Lime & Shale	3384	4065	
Lansing	4065	4120	
Lime	4120	4435	
Base of Kansas City	4435	4439	
Streaks Lime & Shale	4439	4540	
Lime & Shale	4540	4887	
Mississippi Lime	4887	5046	

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 17 1962
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY



Maxine Head
 Maxine Head

Jean Holler
 Notary Public

My Commission Expires:
5-22-66