

15-171-00052-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Scott County, Sec. 3 Twp. 18 Rge. 34 ~~34~~ (W)

NORTH

		X	

Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C NW NE  
 Lease Owner O. H. Parker  
 Lease Name Franklin Well No. 1  
 Office Address 402 A.C. Office Bldg.  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed November 23 1952  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced November 24 1952  
 Plugging completed November 24 1952  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well ?  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				12-3/4"	290'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole was filled with heavy mud. Wooden plug was set with top at 270' and bottom at 272' 25 sacks of cement placed on top of plug. Hole filled with mud. Wooden plug set with top at 30' and bottom at 32' 10 sacks of cement placed on top of plug.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Wood and Hay  
 Address 371 West 3rd. St., Herington, Kansas

STATE OF Kansas, COUNTY OF Cowley, ss.  
Robert L. Jones (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Jones  
402 A.C. Office Bldg., Arkansas City, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of December, 1952

Del B. Roman  
 Notary Public.



**PLUGGING**  
 FILE SEC 3 T 18 R 34  
 BOOK PAGE 62 LINE 11

24-2675-S 2-52-20M


RECEIVED DEC 2 1952  
 CONSERVATION COMMISSION  
 DEC - 3 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

15-171-00052-00-00

WELL LOG - Franklin #1  
C NW NE Sec. 3, T.18-S., R. 34-W.  
Scott County, Kansas

<u>From</u>	<u>To</u>	
0	-	33 Clay
33	-	53 Sand
53	-	155 Sand and Shells
155	-	290 Shale and Shells
290	-	1175 Sand and Shale
1175	-	1565 Shale
1565	-	1620 Red Beds
1620	-	1645 Anhydrite
1645	-	1890 Shale and Salt
1890	-	1995 Shale
1995	-	2070 Lime Shells
2070	-	2175 Shale
2175	-	2300 Shale and Shells
2300	-	2420 Shale
2420	-	2585 Lime and Shale
2585	-	2735 Shale and Lime Shells
2735	-	2750 Lime and Shells
2750	-	2970 Lime and Shale
2970	-	3005 Ft. Riley Dolomite
3005	-	3300 Lime and Shale
3300	-	3365 Shale and Lime
3365	-	3378 Lime and Chert
3378	-	3390 Shale
3390	-	3525 Lime and Shale
3525	-	3610 Shale and Lime
3610	-	3735 Lime and Shale
3735	-	3810 Shale and Lime
3810	-	4015 Lime and Shale
4015	-	4820 Lime
4820	-	4892 Lime and Shale

Driller's T. D. 4892



RECEIVED  
CONSERVATION COMMISSION  
DEC - 3 1952  
CONSERVATION DIVISION  
Wichita, Kansas

DEC 2 1952