

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-171-20275-00-01

API NUMBER N/A

LEASE NAME Sharpe #1

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 2 TWP. 18 SRGE. 33 (E) or (W)

COUNTY Scott

Date Well Completed 1983

Plugging Commenced 10-2-91

Plugging Completed 10-4-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Continental Energy

ADDRESS P. O. Box 918, Garden City, KS 67846

PHONE# (316) 276-8710 OPERATORS LICENSE NO. 5317

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? N/A If not, is well log attached? bought well: No info

Producing Formation KC Depth to Top 4000' Bottom 4100' T.D. N/A

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>N/A</u>		<u>291</u>	<u>surf</u>	<u>8 5/8</u>	<u>291</u>	<u>none</u>
		<u>4100</u>	<u>"</u>	<u>4 1/2"</u>	<u>4100</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sanded up to 3850' well had been cemented to surface: perf 1' 4  
holes @ 1600' pump 200 sks, 60/40 POZ mix 6% gel. Filled 4 1/2"  
to surface. Cut pipe off 6" below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Continental Energy License No. 5317


Address P. O. Box 918 Garden City, KS 67846

STATE OF Kansas COUNTY OF Finney, ss.

Kevin Wiles Sr. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kevin Wiles Sr.

(Address) P.O. Box 918 GARDEN CITY, KS



SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 91

Paula S. Crook  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

OCT 11 1991

CORPORATION DIVISION  
Wichita Kansas

My Commission Expires: 11-30-93