

15-171-20005-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Scott County, Sec. 13 Twp. 19S Rge. 31W ~~2E~~ (W)
Location as "NE/CNW/SW" or footage from lines C NE NE
Lease Owner ~~XXXXXXXXXXXXXXXXXXXX~~ Yucca Petroleum Co.
Lease Name Spitzer Well No. 1
Office Address P. O. Box 2585, Amarillo, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-31-68 19
Application for plugging filed 3-31-68 19
Application for plugging approved 3-31-68 19
Plugging commenced 3-31-68 19
Plugging completed 3-31-68 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4840 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	253'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 100 sks. 50-50 Posmix, 6% gel @ 1110'
25 sks. 50-50 Posmix @ 270'
~~100~~ Bridged @ 40' with Plug & 1/2 sk. hulls, 10 sks 50-50 Posmix, 6% gel

STATE RECEIVED 04-03-68
CONSERVATION COMMISSION
APR 3 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 2nd day of April, 1968.
My commission expires April 1, 1971



Ulanda Nichols
Ulanda Nichols Notary Public.

15-171-20005-00-00

DRILLER'S LOG

COMPANY: YUCCA PETROLEUM COMPANY
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SPITZER #1
 LOCATION: C NE NE SECTION 13-19S-31W
 SCOTT COUNTY, KANSAS
 COMMENCED: 3-18-68
 COMPLETED: 3-31-68

0	110	Surface Clay, Sand
110	525	Shale
525	1306	Blue Shale
1306	1690	Shale
1690	2259	Shale, Shells
2259	2282	Anhydrite
2282	2376	Shale, Lime
2376	2780	Lime, Shale
2780	2925	Lime
2925	3515	Lime, Shale
3515	3670	Shale, Lime
3670	3788	Lime, Shale
3788	3900	Shale, Lime
3900	3986	Chalky Lime
3986	4213	Lime
4213	4373	Lime, Shale
4373	4445	Lime
4445	4511	Lime, Shale
4511	4756	Lime
4756	4785	Lime, Chert
4785	4840	Lime
	<u>4840</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 APR 3 1968
 CONSERVATION DIVISION
 Wichita, Kansas


8 5/8" new 20# surface casing set @ 253' cemented with 225 sacks Common, 3% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Spitzer #1 Well, located C NE NE of Section 13, Township 19 South, Range 31 West, Scott County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
)-SS-
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 2nd day of April, 1968.



Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971