

15-171-00060-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

SCOTT County, Sec. 10 Twp. 19 Rge. 31W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner ATKINSON & OSTRANDER

Lease Name Albert Popp Well No. 1

Office Address c/o W. L. Hartman, P.O. Box 54, Wichita 1, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 15, 1956

Application for plugging filed February 1, 1957

Application for plugging approved February 4, 1957


Plugging commenced February 12, 1957

Plugging completed March 9, 1957

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	
				5-1/2"	4640'	787'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1613 to 1580 ft. Sand
1580 to 1540 ft. 5 sacks cement
1540 to 255 ft. Mudded
255 to 240 ft. Rock bridge.
240 to 195 ft. 15 sacks cement
195 to 15 ft. Mud
15 to cellar 5 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1957

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S Pipe Pulling Company

Address Box 192, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. L. HARTMAN (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *W. L. Hartman*

P.O. Box 54, Wichita 1, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 21st day of March, 1957

My commission expires August 25, 1960

Ella Friess
Ella Friess Notary Public.

PLUGGING
FILE SEC. 10 T. 19 R. 31W
BOOK PAGE 138 LINE 20



CERTIFIED DRILLER'S LOG

COMPANY: ATKINSON & OSTRANDER LEASE: ALBERT POPP #1
 CONTRACTOR: H & H DRILLING COMPANY LOCATION: NE NE SW
 10-19-31W
 Scott County, Kansas
 COMMENCED: 9-11-56
 COMPLETED: 9-29-56 CASING RECORD:
 245' of 8-5/8", cem. w/175 sacks.
 4640' of 5-1/2", cem. w/75 sacks.
 ELEVATION: 2951 R.B.
 POTENTIAL:

<u>FORMATION</u>	<u>DEPTH</u>
Surface Sand	0 - 40
Shale	40 - 960
Shale and Shells	960 - 1490
Shale and Red Bed	1490 - 1675
Shale and Shells	1675 - 2090
Shale	2090 - 2220
Lime and Shale	2220 - 3065
Lime	3065 - 3191
Lime and Shale	3191 - 3289
Lime	3289 - 3683
Lime and Shale	3683 - 3760
Lime	3760 - 4640
RTD	4640

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

B. E. Hartman
 B. E. HARTMAN

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 5th day of October, 1956.

Ella Priess
 ELLA PRIESS, NOTARY PUBLIC



PLUGGING
 FILE SEC 10 T 19 R 31W
 BOOK PAGE 138 LI E 20

RECEIVED
 STATE CORPORATION COMMISSION
 FEB -2 1957
 CONSERVATION DIVISION
 Wichita, Kansas