

P

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 21 1976

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 -171-20, 122-00 (of this well)  
00

Operator's Full Name Car Ren. Inc.  
Complete Address Suite 615 300 W. Douglas, Wichita, Ks.  
Lease Name Watkins Well No. # 1-17  
Location C-NE 4 Sec. 17 Twp. 19 Rge. 31 (E) (W) X  
County Scott Total Depth 2935  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Gabbert Jones, Inc.  
Address      License No.       
Operation Completed: Hour 7:25 AM Day 19 Month Dec. Year 1976

The above well was plugged as follows:

KB. 2973. Dat. Top 1950' SP. 364' of 8 3/8" cwe. 265. SX.  
Pumped down drill stem.  
70. SX. cwe. 50/50 Por mix 6% Gel @ 1100'  
20. " " " " " " " " 300'  
Built Bridge To 40'  
10. SX. cwe. 50/50 Por mix 6% Gel. 40' to 0'

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Gilbert Balthezar  
Well Plugging Supervisor

DATE 12-21-76  
INV. NO. 4363-W