

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED STATE CORPORATION COMMISSION APR 2 1968 CONSERVATION DIVISION Wichita, Kansas

J. P. Roberts Administrator 500 Insurance Building Wichita, Kansas 67202

Operator's Full Name Yucca Petroleum Company,

Complete Address Box # 2585, Amarillo, Texas.

Lease Name Spitzer Well No. 1

Location APP C NE-NE, 560' FNL & 660' FEL Sec. 13 Twp. 19 Rge. (E) (W) 31

County Scott Total Depth 4840'.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 3:15 AM Day 31 Month 3 Year 1968

The above well was plugged as follows:

253'--8 5/8" Surface pipe, cement circulated with 225 Sx. Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1110' and displaced 100 Sx. cement thru DP from 1110' to 790'. Pulled DP to 270' and displaced 25 Sx. cement thru DP from 270' to 195'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar. (Cementing operations performed by Halliburton Company).

I hereby certify that the above well was plugged as herein stated.

Signed: M. D. Nichols Well Plugging Supervisor

INVOICED

DATE 4/2/68 INV. NO. 7515-W