

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-171-29234-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name American Energy's Corp.

Complete Address 575 South Financial Center Wichita Kansas 67202

Lease Name Rush Well No. 1

Location C-SE-NW-NE Sec. 10 Twp. 19 Rge. 31 (East)(West)

County Scott Total Depth 4658'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abecrombie Drilling Inc.

Address 801 Union Center Wichita Kans 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 4:00 A.M. Day: 19 Month: May Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

The anhydrite was topped 2286', The Dakota was topped at 1000'.  
1st plug at 2200' with 35 sbs. of cement. 2nd plug at 1090' with  
35 sbs. of cement. 3rd plug at 360' with 20 sbs. of cement. 4th  
plug on solid ledge at 40' to 0' with 10 sbs. of cement. Then  
circulated 10 sbs. of cement in rat hole. The cement was pumped  
through drill pipe with hole full of heavy mud. The  
plugging was accomplished by Sun Cementing.

Amount of Surface Casing: 328' of 8 1/2" cement circulated with 275 sbs. common cement  
with 3 3/4 sbs. Jella 2 3/4 cc

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Saul A. Luthie  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

The well was out of my area & I was waiting  
on a call on one of my area wells.

INVOICED

DATE 6-3-82

INV. NO. 320-W

Signed: Saul A. Luthie  
Conservation Division Agent

RWD  
05-27-82