

10

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Marsh Oil Associates c/o Davies and Fitzgerald,

Complete Address 1303 Philtower Building, Tulsa, Oklahoma.

Lease Name B. G. Witham Well No. 1
C NE 1/4

Location 1320' FNL & 1320' FEL of NE/4 Sec. 29 Twp. 19 Rge. (E) (W) 31

County Scott Total Depth 2850'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Earl F. Wakefield, Incorporated,

Address 300 W. Douglas, Wichita, Kansas. License No.

Operation Completed: Hour 6.45 PM Day 25 Month 2 Year 1973

The above well was plugged as follows:

357'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 370' and displaced 30 Cu. Ft. cement thru DP
from 370' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. G. Dickel*
Well Plugging Supervisor

INVOICED
DATE 2/28/73
INV. NO. 7056-W