

15-171-20039-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling, Inc., and Petroleum Resources,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Mueller Well No. 1

Location CNE-NW Sec. 26 Twp. 19 Rge. (E) (W) 31

County Scott Total Depth 4800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Bldg., Wichita, Kansas. License No.

Operation Completed: Hour 12:00 M Day 9 Month 1 Year 1972

The above well was plugged as follows:

450'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 165 Cu. Ft. cement
thru DP from 1200' to 725'. Pulled DP to 475' and displaced 45 Cu. Ft. cement thru
DP from 475' to 345'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4979-W