

15-171-30000-00-00

Form CP-3
Rev. 6-26-62

R

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1965
01-15-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name James E. Ely,

Complete Address: Box #127, Sterling, Kansas.

Lease Name James E. Ely Well No. 2

Location CNW-SE Sec. 22 Twp. 19 Rge. (E) (W)³²

County Scott Total Depth 4820

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Group Exploration,

Address: Box #127, Sterling, Kansas. License No.

Operation Completed: Hour 1:30PM Day 11 Month 1 Year 1965

The Above well was plugged as follows:

303'--8 5/8" Surface pipe, cement circulated with 300 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 290', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-15-65

INV. NO. 538-w

Signed: N. L. Nichols
Well Plugging Supervisor