

To: 1 030398  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-18

API NUMBER 15-171-20,462-00-00  
App. 20' W, 150' S  
of NE SE, SEC. 9, T. 7, R. 33  
1830 feet from S section line  
680 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30870  
Operator: Reynolds-Rexwinkle Oil, Inc.  
Name & Address: 212 N. Market, Ste. 402  
Wichita, KS 67202

Lease Name Hansen Well # 1  
County Scott 154.70  
Well Total Depth 4760 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 231

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 8:30 a.m. Day: 18 Month: 2 Year: 19 94

Plugging proposal received from Bill Wynn  
(company name) Murfin Drilling Co. (phone) 316-267-3241

vers: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2200'

1st plug at 2200' with 50 sx cement, 2nd plug at 1380' with 80 sx cement,  
3rd plug at 650' with 40 sx cement, 4th plug at 260' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:45 a.m. Day: 18 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,  
2nd plug at 1380' with 80 sx cement, 3rd plug at 650' with 40 sx cement,  
4th plug at 250' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 02 1994

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE MAR 07 1994

INV. NO. 40084

2-18

Signed \_\_\_\_\_ (TECHNICIAN)

EFFECTIVE DATE: 1-30-94

State of Kansas

171-20,462-00-00

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED

SEAT Yes No

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.S. five (5) days prior to commencing well

Expected Spud Date February 5, 1994 APPX 20 W 150 S NE SE Sec 9 Twp 19 S Rg 33

OPERATOR: License # 30870 Name: Reynolds-Rexwinkle Oil, Inc. Address: 212 N. Market #402 City/State/Zip: Wichita, Kansas 67202 Contact Person: Dan Reynolds Phone: 316-269-1233

CONTRACTOR: License # 6033 Name: Murfin Drilling Company

1830 feet from South line of Section 680 feet from East line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Spott Lease Name: Hansen Well #: 1 Field Name: Wildcat

Is this a Pre-rated/Spaced Field? yes X no

Target Formation(s): Mississippi

Nearest lease or unit boundary: 680

Ground Surface Elevation: 2954 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 140

Depth to bottom of usable water: 1380

Surface Pipe by Alternate: 1 X 2

Length of Surface Pipe Planned to be set: (380) 220'

Length of Conductor pipe required: none

Projected Total Depth: 4700

Formation at Total Depth: Mississippi

Water Source for Drilling Operations: X well farm pond other

DNR Permit to be drilled: not avail yet

Will Cares Be Taken? yes X no

If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment:

- X. Oil ... Erh Rec ... Infield X. Mud Rotary
X. Gas ... Storage ... Pool Ext. ... Air Rotary
... OWD ... Disposal X. Wildcat ... Cable
... Seismic; ... # of Holes ... Other

If OWD: old well information as follows:

Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 7/25/94

AFFIDAVIT

220' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that...

Pusher: Bill W... INIT. SP... LENGTH SURFACE PLANNED 230' of 888... RESERVE PIT STATUS- REMOVE FLUID LINED... RATHOLE AHEAD? Y N SIZE HOLE... SURFACE PIPE 231 CONDUCTOR... ANHYDRITE T- B- 2200 ELEVATION... TD 4760 FORMATION... DRAN PIPE @ DV TOOL ALT II DONE... Arbuckle Plug @ Ft. W/ SX... Hug./Council @ Ft. W/ SX... Anhydrite Base @ 2200 Ft. W/ 50 SX... 1/2 Base Anyh. @ 1380 Ft. W/ 80 SX... 1/2, 1/2 Plug @ 650 Ft. W/ 40 SX... Bottom Surface @ 2600 Ft. W/ 50 SX... 40' Plug @ 40 Ft. W/ 10 SX... RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX... WATER WELL SX (Irr. Well Pond Hauling... TECHNICIAN Sam DATE 2-16-94... TYPE OF CEMENT 60/40 60% 14 F/50... STARTING TIME 8:20 (AM/PM) DATE... COMPLETION TIME 4:15 (AM/PM) DATE 2-18... RECEIVED STATE CORPORATION COMMISSION MARCH 2 1994 CONSERVATION DIVISION Wichita, Kansas