

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-171-00054-00-00
WELL PLUGGING RECORD

SCOTT County. Sec. 10 Twp. 19 Rge. 31W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner H & H Drilling Company

Lease Name Rush Well No. 1

Office Address P.O. Box 54, Wichita 1, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed November 1, 19 54

Application for plugging filed February 1, 19 57

Application for plugging approved February 4, 19 57

Plugging commenced March 10, 19 57

Plugging completed March 15, 19 57

Reason for abandonment of well or producing formation
No longer considered commercial.

If a producing well is abandoned, date of last production February 8, 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage

Producing formation Arbuckle Depth to top 5043 Bottom 5054 Total Depth of Well 5081 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	
				5-1/2"	5078'	3272'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4586 to 4560 ft. Sand
4560 to 4520 ft. 5 sacks cement
4520 to 255 ft. Mudded
255 to 245 ft. Rock Bridge
245 to 185 ft. 20 sacks cement
185 to 15 ft. Mud
15 to cellar 5 sacks cement.



(If additional description is necessary use BACK of this sheet)
Name of Plugging Contractor R & S Pipe Pulling Company
Address Box 192, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. E. HARTMAN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *R. E. Hartman*
P.O. Box 54, Wichita 1, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 21st day of March, 1957

My commission expires August 25, 1960

Ella Priess
Ella Priess Notary Public.



PLUGGING
FILE SEC. 10 T. 19 R. 31W
BOOK PAGE 44 LINE 18
138

15-171-00054-00-00

CERTIFIED DRILLER'S LOG

COMPANY: H & H DRILLING COMPANY
CONTRACTOR: H & H DRILLING COMPANY
COMMENCED: 9-10-54
COMPLETED: 10-12-54
ELEVATION: 2942 R.B.
POTENTIAL:

LEASE: RUSH #1
LOCATION: NW NW NE
10-19-31W
Scott County, Kansas

CASING RECORD:
245' of 8-5/8", cemented w/200 sacks
5078' of 5-1/2", cemented w/300 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Clay	0 - 15
Shale	15 - 98
Sand	98 - 105
Shale	105 - 1325
Sand	1325 - 1450
Red Bed and Shale	1450 - 1660
Shale	1660 - 2190
Shale and Red Bed	2190 - 2287
Red Bed	2287 - 2345
Shale	2345 - 2511
Shale and Shells	2511 - 2655
Shale and Lime	2655 - 2780
Lime	2780 - 2795
Lime and Shale	2795 - 2922
Lime	2922 - 4804
Lime and Chert	4804 - 4822
Chert	4822 - 4827
Lime and Chert	4827 - 4887
Lime	4887 - 5078
RTD	5078

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

R. E. Hartman
R. E. HARTMAN

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1957

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SS

Subscribed and sworn to before me this 16th day of October, 1954.

PLUGGING
FILE SEC 10 T 19 R 31W
BOOK PAGE 138 LINE 18

Ella Press
Notary Public

My Commission Expires: August 25, 1956