

API NUMBER 15-171-30068-00-00

LEASE NAME Wise

WELL NUMBER 1-6

SPOT LOCATION C NW NW SE

SEC. 6 TWP. 19 RGE. 31 XX or (W)

COUNTY Scott

Date Well Completed 11-30-1966

Plugging Commenced 3-30-89

Plugging Completed 4-5-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Unico Inc.

ADDRESS Box 35, Farmington, NM 87499

PHONE # (303) 980-1277 OPERATORS LICENSE NO. 3857

Character of Well gas
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filled? yes If not, is well log attached? _____

Producing formation Hugoton NE Depth to top 2754 bottom 2782 T.D. 2825

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	240'	0'
Production				4 1/2"	2825'	1452'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 20 sks. cement to 2450' and pressure to 500 lbs.
Pump 80 sks. cement 1400' to 1200' - mud 1200' to 270'
Pump 40 sks. cement 270' to 170' - mud 170' to 40'
Put bridge and 10 sks. 40' to 3' - cut off 8 5/8", 3' below ground level and cap

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497
 Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (XXXXXXXXXXXXXXXXXXXX) or (operator) of above-described well, **RECEIVED STATE CORPORATION COMMISSION** sworn on oath, says: That I have knowledge of the facts, state, operation and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

MAY 15 1989

(Signature) Edgar J. Eves
 (Address) Box F, Sublette, Ks. 67877



CONSERVATION DIVISION
 Wichita, Kansas.
 SUBSCRIBED AND SWORN TO before me this 10th day of April, 1989
Sondra L. Eves
 Notary Public

My Commission expires: 12-6-92