

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-171-30061-00-00

LEASE NAME Stucky #1-5

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NW

SEC. 5 TWP. 19 S. RGE. 31 W (E) or

COUNTY Scott

Date Well Completed \_\_\_\_\_

Plugging Commenced 5/16/84

Plugging Completed 5/17/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Cargill Natural Gas Operations bought by Kelso  
Casing Pulling  
ADDRESS 604 One Main Place, Wichita, Ks. 67202

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, S&D, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 2826'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	250'	none
				4 1/2"	2825'	863.99'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged bottom with sand to 2225' & ran 4 sacks cement. Shot pipe at 1537'  
1001' & 864'. Pulled 26 joints of pipe. Plugged well with 2 hulls, 10 gel,  
50 cement, 10 gel, 1 hulls plug, & 225 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1984



Irene Hoover  
Notary Public

My Commission expires \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

MAY 23 1984

CONSERVATION DIVISION  
Wichita, Kansas

STENTENGELED

JAN 6 1968  
JAN 6 1968

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
308 EAST MURDOCK - WICHITA, KANSAS

ORIGINAL

15-171-30061-0000

SEC. 5 T. 19 S. 31W  
LOC. C NW

COMPANY KATEX OIL CO.

FARM Stucky NO. 1

TOTAL DEPTH 2822'

COMM. 7-2-66


SHOT OR TREATED

CONTRACTOR Murfin Drlg.

ISSUED 1-6-68

COMP. 9-22-66

COUNTY SCOTT



K.G.S. LIBRARY

CASING

20 10  
15 8 5/8  
12 6

240'

ELEVATION 2966' GR

2800' w/100' ex cem. PRODUCTION GA 1,500

MCFGPD (CHASE 2775)

FIGURES INDICATE BOTTOM OF FORMATIONS

COMPLETE DRILLERS LOG NOT AVAILABLE.

TOPS: SCOUT	2292
B/Cimarron	2731
Hollenberg	2742
Herrington	2769
Krider	2794
B/Krider	2816
Winfield	