

15-171-00072-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Scott County. 5 Twp. 19 Rge. (E) 31 (W)
Location as "NE/CNW*SW*" or footage from lines C SW NW
Lease Owner Pickrell Drilling Company
Lease Name Stucky "B" # Well No. 1
Office Address 705 4th National Bank Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 31, 1963
Application for plugging filed August 31, 1963
Application for plugging approved August 31, 1963
Plugging commenced August 31, 1963
Plugging completed August 31, 1963
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	283'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 280'. Set plug. Cemented with
20 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 13 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Bldg, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. SEBITS
705 4th National Bank Bldg, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of September, 19 63
Ruth M. Sullivan
Notary Public.



ROTARY DRILLING LOG

15-171-00072-00-00
 Rotary Drilling Commenced 8-16-63
 Rotary Drilling Completed 8-30-63

COMPANY: PICKRELL DRILLING COMPANY
 705 4th NATIONAL BANK BLDG
 WICHITA 2, KANSAS
 LOCATION: STUCKY "B" No. 1
 C SW NW 5-19-31W, Scott County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (10 jts) 8 5/8" surface casing set at 283', cemented with 185 sacks cement. Circulated. Completed 3:45 P.M. August 16, 1963, no oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

120	Clay - Sand	
150	Ft. Hays	<u>C. F. S.</u>
280	Shale & Shells	3950
650	Shaly, Shells	4036
990	Shale	4051
1475	Shale & Shells	4070
1725	Sandy Shale	4172
1765	Blaine	4200
2000	Shale & Shells	4230
2235	Shale	4400
2280	Shale & Shells	4555
2305	Anhydrite	4565
2415	Shale & Shells	4584
2565	Shale & Lime	4660
2755	Limy Shale	
2810	Lime & Sand	<u>Slope Tests</u>
2918	Shale & Lime	2500
3390	Lime	3000
3950	Lime & Shale	3500
4308	Lime	4000
4430	Lime & Shale	
4515	Lime	
4584	Lime & Shale	<u>S. L. M.</u>
4660	Mississippian - RTD	3297
		3832
		4444

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 30 1963
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 5th day of September, 19 63, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1965

[Signature]
 Ruth M. Sullivan Notary Public