


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

15-171-19014-00-00

NORTH



Locate well correctly on above
Section Plat

Scott

County. Sec. 3 Twp. 19S Rge. 31W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner H & H DRILLING COMPANY

Lease Name JANSSEN Well No. 1

Office Address P.O. Box 54, Wichita 1, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil well

Date well completed August 12, 19 55

Application for plugging filed February 1, 19 57

Application for plugging approved February 4, 19 57

Plugging commenced February 23, 19 57

Plugging completed March 2, 19 57

Reason for abandonment of well or producing formation

No longer considered commercial.

If a producing well is abandoned, date of last production February 8, 19 57

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Miss Depth to top 4593 Bottom 4595 Total Depth of Well 4685 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	245'	
				5-1/2"	4685'	2832'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4617 to 4580 ft. Sand Bridge
4580 to 4540 ft. 5 sacks cement
4540 to 255 ft. Mudded
255 to 245 ft. Rock Bridge
245 to 185 ft. 20 sacks cement
185 to 20 ft. Mud
20 ft. to cellar 5 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1957
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor R. & S. Pipe Pulling Company
Address Box 192, Ellinwood, Kansas

03-12-57

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. E. HARTMAN (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. E. Hartman
P.O. Box 54, Wichita 1, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of March, 19 57

Ella Priess Notary Public.



PLUGGING
FILE SEC 3 T 19 R 31W
BOOK PAGE 138 LINE 17

15-171-19014-00-00

CERTIFIED DRILLER'S LOG

COMPANY: H & H DRILLING COMPANY

LEASE: JANSSEN #1

CONTRACTOR: H & H Drilling Company

LOCATION: SW SW SE
Sec. 3-19S-31W
Scott County, Kansas

COMMENCED: 7-12-55

COMPLETED: 7-29-55

ELEVATION: 2947 RB

CASING RECORD:

245' of 8-5/8", cem. w/200 sacks.
4685' of 5-1/2", cem. w/100 sacks.

POTENTIAL:

FORMATIONDEPTH

Clay	0 - 15
Shale	15 - 82
Sand	82 - 120
Shale	120 - 245
Shale and Sand	245 - 1565
Shale	1565 - 1990
Shale and Shells	1990 - 2520
Shale and Lime	2520 - 3069
Lime	3069 - 3466
Shale and Lime	3466 - 3574
Lime	3574 - 3643
Lime and Shale	3643 - 3710
Lime	3710 - 4685
RTD	4685


I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

R. E. Hartman
R. E. HARTMAN

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me this 13th of August 1955.

Ella Priess
ELLA PRIESS, NOTARY PUBLIC



Commission Expires: August 25, 1956.

PLUGGING

FILE SEC 3 T 19 R 31W
BOOK PAGE 138 LINE 12

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1957

CONSERVATION DIVISION
Wichita, Kansas