

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-171-20242-000

LEASE NAME Steinberg

WELL NUMBER #1 Twin

SPOT LOCATION 100' SW of C-NW/4

SEC. 2 TWP. 19 RGE. 31 (E) (W)

COUNTY Scott

Date Well Completed 1-6-83

Plugging Commenced 2-17-84

Plugging Completed 2-17-84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR A.L. Abercrombie, Inc.

ADDRESS Rt. #1, Box 56, Great Bend, Kansas 67530

PHONE (316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? yes

Producing formation Marmaton Depth to top 4318 bottom 4478 T.D. 4500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 360 | None |
| | | | | 5 1/2 | 4498 | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 5 1/2 set @ 4498, perfs. @ 4384-90 & 4396-4400 D.V. tool @ 1513. Circulated cement to surface. Top plug pump 2 sx hulls, 30 sx cement, 20 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls and pump on additional 125 sx. cement. Maximum pressure 100# and shut in pressure 0#. Used 60/40 pos mix 2% gel, 3% ca cl. by turn cementing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor A.L. Abercrombie, Inc. License No. _____
 Address Rt. 1, Box 56, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Jack K. Wharton (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

STATE CORPORATION COMMISSION
 RECEIVED
 MAR 28 1984

(Address) 801 Union Center Wichita, KS 67202
 SUBSCRIBED AND SWORN TO before me this 27 day of March, 1984

JoAnn E. Berner
 Notary Public

JoAnn E. Berner



My Commission expires: July 18, 1987.