

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Scott County, Sec. 22 Twp. 19S Rge. 32W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW SE  
Lease Owner James E. Ely  
Lease Name Ely Well No. 2  
Office Address c/o Sterling Drilling Company, Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 11 19 65  
Application for plugging filed January 11 19 65  
Application for plugging approved January 11 19 65  
Plugging commenced January 11, 11:00 a.m. 19 65  
Plugging completed January 11, 3:00 p.m. 19 65  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4820 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	303'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud up to 600', 20 sacks cement at 600'. Heavy mud up to 290'  
20 sacks cement, Halliburton plug at 290'. Heavy mud up to 40',  
Halliburton plug at 40' and 10 sacks cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1965  
01-18-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
Address Box 127, Sterling, Kansas


STATE OF KANSAS, COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
Box 127, Sterling, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of January, 19 65

My Commission Expires Jan. 22, 1966  
BERNARD LAUDERMILK

Bernard Laudermilk  
Bernard Laudermilk, Notary Public.



15-171-30000-00-00

STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG ----- Ely #2

LOCATED: C NW SE Section 22-19S-32W, Scott County, Kansas

OWNER: James E. Ely  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: December 26, 1964  
COMPLETED: January 11, 1965

ROTARY TOTAL DEPTH: 4820'

LOG

CASING RECORD

0 - 308	Shale & Shells
308 - 875	Shale
875 - 1418	Shale & Shells
1418 - 1697	Shale & Lime
1697 - 2285	Shale & Shells
2285 - 2608	Shale & Lime
2608 - 2680	Anhydrite
2680 - 2779	Shale & Shells
2779 - 3030	Lime & Shale
3030 - 3116	Lime with Shale & Shells
3116 - 3260	Lime
3260 - 3344	Shale with Streak of Chalk
3344 - 3395	Lime & Shale
3395 - 3520	Lime & Sand
3520 - 3705	Shale & Lime
3705 - 3830	Shale with Lime & Chalk
3830 - 4077	Lime & Chalk
4077 - 4465	Lime
4465 - 4512	Lime & Sand
4512 - 4580	Lime
4580 - 4610	Lime & Shale
4610 - 4665	Lime
4665 - 4707	Lime & Chert
4707 - 4820	Lime T. D.

Ran 8 5/8" Surface Casing at 303' K.B.  
with 150 sacks Pozmix 2% c.c.

Dry and Abandoned