

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-171-20056-0000

LEASE NAME McCutchen

WELL NUMBER A #1

SPOT LOCATION C SW SW-SE

SEC. 12 TWP. 19 RGE. 32 (X) or (W)

COUNTY Scott

Date Well Completed 1973

Plugging Commenced 4-28-89

Plugging Completed 5-2-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Unico Inc.

ADDRESS 1921 Bloomfield, Farmington, NM 87401

PHONE # (303) 980 1277 OPERATORS LICENSE NO. 3857

Character of Well gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Krider Depth to top 2700 bottom 2768 T.D. 4053

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	555'	0'
Production				5 1/2"	4053"	1340'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 25 sks. cement to 2500' - pressured to 500 lbs. Mud to 1340'

Pump 80 sks. cement @ 1340' Mud to 570'

Pump 40 sks. cement @ 570' Mud to 40'

Put bridge and 10 sks. cement 40' to 3'

Cut off 8 5/8", 3' below ground level & cap

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497

Address Box F, Sublette, Ks. 67877

RECEIVED

STATE OF KANSAS COUNTY OF Haskell, ss.

STATE CORPORATION COMMISSION

I, Edgar J. Eves

(~~employee of operator~~) or

JUL 10 1989

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877



SUBSCRIBED AND SWORN TO before me this 5th day of May, 1989

Sondra L. Eves  
Notary Public

My Commission expires: 12-6-92