


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-171-00056-00-00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Scott County, Sec. 9 Twp. 19 Rge. 32 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE. 1/4, NE. 1/4, SW. 1/4
Lease Owner DR. Robinson Etal
Lease Name Kinzel Well No. I
Office Address Scott City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Rotary Dry Hole
Date well completed 9/5/1950
Application for plugging filed 9/5/1950
Application for plugging approved 9/5/1950
Plugging commenced 9/6/1950
Plugging completed 9/6/1950
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production X 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation None Depth to top X Bottom X Total Depth of Well 491.4 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sands soil & Gravels	Fresh Water	00	275	10 3/4	310	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with heavy rotary mud from (T.D. 491.4') back to 310' where a bridging plug was set and 25 sacks cement was put in hole through the drill pipe filling the surface casing back to 240'. The surface casing was then filled with rotary mud to within 10' of the top and another bridging plug was set and 10 sacks cement was dumped filling the top of the surface casing and the bottom of the cellar.

The surface casing was cemented from top to bottom at the time it was run

RECORDED
SEP 15 1950 09-15-50
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbor Drilling Company

Address 1019 Central Bldg.
Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
I, W. M. Barnett (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. M. Barnett

SUBSCRIBED AND SWORN to before me this 8th day of September, 1950
My commission expires 9-4-54
Ray Gillig Notary Public



PLUGGING
FILE SEC 9 T 19 R 32 W
BOOK PAGE 26 LINE 26

KINZEL NO. 1

NE $\frac{1}{4}$ NE $\frac{1}{4}$ SW $\frac{1}{4}$ Sec. 9-19-32W, Scott County, Kansas

Rigging up Rotary Tools 8-17-50
 Tearing down Rotary Tools 9-7-50

Run 10 Jts. 311' of 10 3/4" surface casing.
 Set at 310' and cemented with 150 sx cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface sand and gravel	0	197
Shale and shells	197	310
Sand and gumbo	310	1290
Shale and sand	1290	1540
Shale	1540	1700
Shale and lime	1700	1800
Lime	1800	1825
Shale and lime	1825	2060
Redbed, shale and shells	2060	2225
Shale and red rock	2225	2380
Shale and shells	2380	2955
Lime and shale	2955	3290
Cherty shale and lime	3290	3375
Lime	3375	3460
Shale and lime	3460	3650
Lime	3650	3710
Shale and lime	3710	3830
Lime	3830	3900
Shale and lime	3900	3980
Lime	3980	4080
Lime Chert	4080	4108
Lime and shale	4108	4200
Lime	4200	4220
Lime and shale	4220	4075
Lime	4075	4505
Lime and Cherty Shale	4505	4545
Lime, Shale and Chert	4545	4590
Lime and shale	4590	4610
Lime	4610	4900
Lime and Chert	4900	4914 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.


Don S. Packer

Subscribed and sworn to before me this 14th day of September, 1950.

Nelson Kelly

 Notary Public

My commission expires: March 22, 1952



RECEIVED

SEP 15 1950

STATE COMMISSION
 KANSAS

PLUGGING
 FILE SEC 9-T-19-R-32W
 BOOK PAGE 26 LINE 26