

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-171-00045-00-00
WELL PLUGGING RECORD

Scott County, Sec. 1 Twp. 19S Rge. 32W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE SW

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Strickert Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 10, 1956

Application for plugging filed November 10, 1956

Application for plugging approved November 10, 1956


Plugging commenced November 10, 1956

Plugging completed November 10, 1956

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundege, Box 283, Hoisington, Ks.

Producing formation Depth to top Bottom Total Depth of Well 4760 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	11-10-56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set No. 1 plug at 530' with 20 sacks cement. Set No. 2 plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1956

11-17-56

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 903 Union National Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) BZ: *Ray L Bacon* V-P
903 Union National Bldg., Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1956

My commission expires April 18, 1959

Frances E. Barham
Frances E. Barham Notary Public.

PLUGGING
FILE SEC 1.1.19 R 32W
BOOK PAGE 115 L E 26

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Building
Wichita 2, Kansas

Strickert No. 1
SW SE SW Section 1-19S-32W
Scott County, Kansas

Total Depth: 4760'

Elevation: 2974' R.B.

Commenced: 10-20-56 Completed 11-10-56

Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 619' with 350 sacks cement.

Figures indicate bottom of formations:

Sand, Shale & Shells	619'		
Shale & Shells	1030'		
Anhydrite	1790'		
Shale & Shells	2735'		
Shale & Lime	3965'		
Lime	4030'		
Lime & Shale	4068'		
Lime	4460'		
Lime & Shale	4490'		
Lime	4500'		
Lime & Shale	4618'		
Lime	4760'		
Total Depth	4760'		

		<u>TOPS</u>	
	Anhydrite		1745' (/1229)
	Hallenberg		2755' (/ 219)
	Herrington		2781' (/ 193)
	Heebner		3933' (- 959)
	Lansing		3976' (-1002)
	Cherokee		4512' (-1538)
	Mississippi		4625' (-1651)
	Total Depth		4760' (-1786)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

PLUGGING			
FILE	SEC	T. 19	R. 32W
BOOK	PAGE	115	LINE 26

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Dyer
Vice President

Subscribed and sworn to before me this 16th day of November, 1956.

My Commission Expires:

April 18, 1959

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1956

CONSERVATION DIVISION
Wichita, Kansas

Frances E. Barber
Notary Public