


15-171-20084-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

### WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Scott County, Sec. 14 Twp. 19S Rge. (E) 33 (W)  
Location as "NE/CNW/SW" or footage from lines: C SW NW  
Lease Owner: Maurice L. Brown Company  
Lease Name: Collingwood Trust  
Office Address: 1500 Vickers/KSB&T Bldg., Wichita, Ks.  
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole  
Date well completed: October 26, 1975  
Application for plugging filed: 19  
Application for plugging approved: 19  
Plugging commenced: October 26, 1975  
Plugging completed: October 26, 1975  
Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Clarence Thomas of Garden City)

Name of Conservation Agent who supervised plugging of this well:  
Producing formation: Depth to top: Bottom: Total Depth of Well: 5050 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	356.49	8-5/8"	356.49	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Plugged hole w/60 sax cement @ 900 Feet,  
35 sax cement @ 400 Feet, 15 sax cement  
40 Feet to 0, 2 sax cement in Rat Hole.  
Job Completed @ 4:30 A.M.

Name of Plugging Contractor: Halliburton  
Address: R.R.1, Box 112, Liberal, Ks.

STATE OF KANSAS COUNTY OF SEDGWICK  
T. McCaul, Jr. of Sage Drilling Co. ss.

Subscribed and sworn to before me this 31st day of October 1975.

(Signature) T. McCaul, Jr.  
500 Bitting Bldg., Wichita, Kansas (Address)



(Signature) Louise K. Whitted  
Louise K. Whitted - Notary Public.

My commission expires November 26, 1978.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 7 1975  
11-07-75  
CONSERVATION DIVISION  
Wichita, Kansas

15-171-20084-00-00

DRILLERS LOG

COLLINGWOOD TRUST NO. 1

CASING RECORD:	OPERATOR: Maurice L. Brown Co.	DESCRIPTION:
8-5/8" set @ 356.49' w/300 sax cement	CONTRACTOR: Sage Drilling Co.	C SW NW Sec. 14-19S-33W Scott Co., Kansas
TOTAL DEPTH: 5050'	COMMENCED: October 12, 1975	ELEVATION: 2952KB
	COMPLETED: October 26, 1975	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Sand	0	100	
Sand	100	361	
Shale	361	762	
Sand	762	1685	
Shale & Sand	1685	2689	
Shale & Lime	2689	3245	
Lime	3245	3370	
Lime & Shale	3370	3535	
Shale & Lime	3535	3690	
Lime	3690	4643	
Lime & Shale	4643	4772	
Lime	4772	5050	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED  
STATE CORPORATION COMMISSION

SAGE DRILLING CO., INC.

NOV 7 1975

CONSERVATION DIVISION  
Wichita, Kansas

By T. M. McCaul, Jr.  
T. M. McCaul, Jr.



Subscribed and sworn to before me this 31st day of October, 1975.

Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1978.