


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-171-20085-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Scott County, Sec. 12 Twp. 19 Rge. 33 R/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
330' FWL & 430' FSL NW 1/4  
Lease Owner The Maurice Brown Co. & Wayne Woolsey  
Lease Name Hushaw Well No. 1  
Office Address 200 Sutton Place Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Gas  
Date Well completed 1-21-76 SIGW 19  
Application for plugging filed 9-10-82 19  
Application for plugging approved 9-13-82 19  
Plugging commenced 10-14-82 19  
Plugging completed 10-19-82 19  
Reason for abandonment of well or producing formation  
Non Commercial Value  
If a producing well is abandoned, date of last production  
Not a producing well. 19  
Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Luthi  
Producing formation Hugoton Depth to top 2721' Bottom 2886' Total Depth of Well 5050'  
Show depth and thickness of all water, oil and gas formations. 2725

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface			5	8 5/8"	356'	0'
Production	Gas	2721	2725	5 1/2"	2956'	500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 2 sks. hulls & 25 sks. cement to 2625' Pressured to 750 lbs.  
Recovered 500' of 5 1/2" casing  
Pumped 85 sks. cement 500' to 200'  
Put bridge & 10 sks. cement 40' to 0'  
Weld plate on 8 5/8", 3' below ground level

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1982

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service  
Op. Lic. 6497

STATE OF KANSAS COUNTY OF HASKELL, ss.  
I, Edgar J. Eves (employee or owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves  
Box F, Sublette, Ks. 67877  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of Oct., 19 82

Sandra L Eves  
Notary Public.

My commission expires 12-6-84



15-171-20085-00-00

DRILLERS LOG

HUSHAW NO. 1

CASING RECORD:	OPERATOR: Maurice L. Brown Co.	DESCRIPTION:
8-5/8" set @ 356' w/300 sax cement	CONTRACTOR: Sage Drilling Co.	330' E of WL & 430' N of SL of NW¼ Sec. 12-19S-33W Scott County, Kansas ELEVATION: 2947KB
TOTAL DEPTH: 5055'	COMMENCED: November 13, 1975	
	COMPLETED: November 30, 1975	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	361	
Shale	361	570	
Shale & Sand	570	1870	
Sand & Shale	1870	2280	
Shale & Lime	2280	2575	
Lime & Shale	2575	2855	
Lime	2855	2935	
Lime & Shale	2935	3185	
Shale & Lime	3185	3314	
Lime	3314	3465	
Shale & Lime	3465	3615	
Lime & Shale	3615	3980	
Shale & Lime	3980	4100	
Lime & Shale	4100	4215	
Lime	4215	4320	
Shale & Lime	4320	4345	
Lime & Shale	4345	4490	
Lime	4490	4760	
Shale & Lime	4760	4885	
Lime	4885	5055	

5½" set @ 2956'  
w/150 sax cement

RECEIVED  
STATE CORPORATION COMMISSION

SFP 3 1982


CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

*T. M. McCaul, Jr.*

By \_\_\_\_\_  
T. M. McCaul, Jr.



Subscribed and sworn to before me this 10th day of December, 1975.

*Louise K. Whitted*  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1978.