

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-171-20.179-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Scott County, Sec. 11 Twp. 19S Rge. 33W. E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW

Lease Owner The Maurice L. Brown Company
Lease Name COLLINGWOOD "C" Well No. 1
Office Address 200 Sutton Place, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Sep. 19 1979
Application for plugging filed (verbally) Sep. 19 1979
Application for plugging approved (verbally) Sep. 19 1979
Plugging commenced Sep. 19 1979
Plugging completed Sep. 19 1979

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2920'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 2920'
Set 1st plug at 840' with 70 sacks
2nd plug at 360' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 9:45 a.m., 09-19-79.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 79



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires: 08-21-82

15-171-20179-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	The Maurice L. Brown Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Collingwood "C" #1
LOCATION:	C SW, Section 11-19S-33W Scott County, Kansas
SPUD DATE:	September 13, 1979
COMPLETION DATE:	September 19, 1979

0	185	Sand and shale
185	367	Shale and sand
367	850	Shale
850	2260	Shale and sand
2260	2278	Anhydrite
2278	2334	Shale
2334	2750	Shale and lime
2750	2920	Lime and shale
	2920	Rotary Total Depth

Spud hole at 1:45 p.m., September 13, 1979. Drilled 367' of 12 1/4" hole. Ran 9 joints of 8-5/8" - 22.63# casing. Set at 366.50' with 150 sacks of Halliburton lite, 2% Ca.Cl., 1/4# flocel. Followed with 150 sacks of common cement, 3% Ca.Cl., 1/4# flocel. Cement did circulate. Plug was down at 9:15 p.m., September 13, 1979.

T.D. 2920'. Set 1st plug at 840' with 70 sacks, 2nd plug at 360' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:45 a.m., September 19, 1979.

SAMPLE TOPS:

Anhydrite	2260'
B/Anhydrite	2278'

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1979

CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Collingwood "C" #1, C SW, Section 11-19S-33W, Scott County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 24th day of September, 1979.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 08-21-82.