

API NUMBER 15-171-20,455-60-60

LEASE NAME Metzger

WELL NUMBER 1-11

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 11 TWP. 19S RGE. 33 ~~(S)~~ or (W)

COUNTY Scott

Date Well Completed 5-19-93

Plugging Commenced 5-19-93

Plugging Completed 5-19-93

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR McCoy Petroleum Corporation

ADDRESS 110 S. Main, Suite 500, Wichita, KS 67202

PHONE#(316) 265-9697 OPERATORS LICENSE NO. 5003

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-18-93 (date)

by Richrd Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	386'	8-5/8"	386'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged and abandon using 60/40 Pozmix, 6%gel, 1/4# flocele per sack. 1st plug @ 2270' w/50 sks; 2nd plug @ 1350' w/80 sks; 3rd plug @ 410' w/50 sks; 4th plug @ 40' w/10 sks. 15 sacks in rathole, 10 sacks in mouse hole. Plugging complete 5-19-93.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sweetman Drilling, Inc. License No. 5658

Address 110 S. Main, Suite 500, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(RECEIVED)  
 STATE CORPORATION COMMISSION  
 (Address) 110 S. Main, Suite 500, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24 day of May, 19 93



Deborah Ann Paulus  
 Notary Public  
 Wichita, Kansas

My Commission Expires 1-8-96